VOLTLINE CHARGING · DATA SHEET · OCT 2026

Workplace Post 22 kW

From $4,850 per post installed - two bays per post, trenching and permit quoted up front

Twin-socket AC post for offices, apartments and hotels. Up to 75 miles an hour, car allowing; drivers pay per kWh in the app and the site is paid out monthly. Up to 24 bays share one 100 A feed.

CHARGING

Output	**22 kW AC per post**
Sockets	**2 - one per bay**
Miles per hour	**Up to 75, car allowing**
Cables	**J1772 or NACS**
Load management	**Up to 24 bays on 100 A**
Scheduling	**Per bay or site-wide**

POST

Size (H x W x D)	**1,400 x 300 x 220 mm**
Weight	**38 kg**
Casing	**IP65 - IK10 impact rated**
Operating range	**-30 °C to 50 °C**
Mounting	**Pedestal or wall pair**

BILLING & ACCESS

Driver payment	**Per kWh in the app**
Payouts	**Monthly to the site**
Access	**Public, staff-only or both**
Reporting	**Monthly kWh per bay**

WARRANTY

Parts & labour	**3 years**
Remote diagnostics	**For life**
Typical 12-bay site	**Live in 5 weeks**

Voltline Charging · 1180 Meridian Road, Unit 4, Oakfield, CA 95000 · hello@voltlinecharging.example · +1-555-0163
Licensed electrical contractor Lic. #C10-882140. State and utility rebates vary - checked per address. Demo content.